OFFICE OF THE CHIEF ENGINEER, BANGALORE WATER SUPPLY AND SEWERAGE BOARD, BANGALORE.

Notice dated 21st February 1969.

Intending Tenderers for the work of constructing Water Transmission mains for Cauvery Water Supply Scheme under Bangalore Water Supply and Sewerage Board, are hereby informed that the work on providing and laying (1) the gravity main from Netkal Balancing Reservoir to Thorekadanahalli and (2) the transmission main from Thorekadanahalli to Bangalore in three consecutive lengths including trunk mains within the City of Bangalore is proposed to be taken up forthwith.

The approximate details of the items of work are as under.

CAUVERY WATER SUPPLY SCHEME.

First Stage (30 M.G.D.)

Sl. No.	Item of work	Nature of work involved	Approximate Dimensions	Approximate cost in million rupees	Approximate period for completion of work
1	2	3	4	5	6
1	Providing and laying gravity main from Netkal Balancing Reservoir to Thorekadanahally including allied works for transmission of 66 M.G.D.	(a) Steel pipes or (b) Pre-stressed Concrete pipes	9.7 Kilometres length of 1750 millimetres clear dia. (Max. working head 35 metres)	13.0 in case of Steel Pipes or 8.0 in case of Pre-stressed Concrete pipes.	36 months
2	Transmission main for 30 M.G.D from treatment site pumping station at Thorekadanahalli to the 2nd Pumping Station near Harohalli.	(a) Steel Pipes or (b) Pre-stressed Concrete Pipes	43.5 Kilometres length of 1.00 millimetres clear dia (Max. working head 250 meters)	37.0 in case of Steel Pipes or 29.0 in case of Pre stressed Concrete Pipes	36 months
3	Transmission main for 30 MGD. from 2nd Pumping Station to the 3rd Pumping Station near Tataguni	(a) Steel Pipes or (b) Pre-stressed Concrete Pipes	21 Kilometres of length 1200 millimetres clear dia. (Max. working head 230 metres).	18.0 in case of Steel Pipes or 14.0 in case of Pre-stressed Concrete Pipes.	36 months
4	Transmission main for 30 M.G.D. from 3rd Pumping Station to South End Terminal point of Bangalore City.	(a) Steel Pipes or (b) Pre-stressed Concrete Pipes.	13 Kilometres of length 1200 millimeters clear dia. (Max. working head 230 metres)	11.0 in case of Steel Pipes or 9.0 in case of Pre-stressed Concrete Pipes.	36 months
5	(i) Trunk Mains in the City	(a) Steel Pipes or (b) Pre-stressed Concrete Pipes	4.8 Kilometres of length 900 millimetres clear dia. and 6.4 Kilometres of length 1200 millimetres clear dia. (Max working head 75 metres)	8.00 in case of Steel Pipes or 5.80 in case of Pre-stressed Concrete Pipes.	24 months
5	(ii) Trunk Mains in the City	C. I. Pipes	8 Kilometres of length 600 millimetres clear dia and 4.8 Kilometres of length 75.0 millimeteres clear dia. (Max. working head 75 metres)	5.00	24 months

The above 5 items of work can be tendered induvidually or collectively. The final decision of allotment of the work either individually or collectively vests with the competent authority to dispose of the tenders.

Intending tenderers should preferably have previous experience of work of similar nature and magnitude and should preferably be on the approved list of the State P.W D., C.P.W.D., Railways or other Government and Quasi-Government Departments. Foreign Firms as well as Indian Firms having foreign collabration and capable of executing the above items of work are also eligible to tender. Intending tenderers are requested to study forthwith the site conditions and relevant information available in the Office of the Chief Engineer, Bangalore Water Supply and Sewerage Board, M.G.I.D. Building Annexe, Bangalore. with immediate effect. Detailed tender documents including specifications, drawings, etc., will be issued from the Office of the Chief Engineer, B.W.S.S.B. with effect from 9th April 1969, and will be returnable to the Office of the Chief Engineer, Bangalore Water Supply and Sewarage Board, by 9th July 1969.

The E.M.D. to be paid along with the tender will be 1 per cent of the estimated cost of the work deposited in cash in favour of the Chairman, Bangalore Water Supply and Sewerage Board in the State Bank of Mysore, Vidhana Veedhi, Bangalore-1, or in the form of Bank Draft in favour of the Chairman, Bangalore Water Supply and Sewerage Board.

It is open to intending tenderers to submit their alternative designs conforming to the general specifications, materials, working heads and capacities etc., mentioned above.

The job involves procurement of materials and fabrication equipment, fabrication of pipes, excavation, laying of pipes and jointing of pipes including providing and fitting all types of valves and specials etc., as per drawings.

Intending tenderers should also specify minimum foreign exchange requirements if any for the various items of work including special terms of collaborations if any etc.

P713 ...., *Chief Engineer.*

OFFICE OF THE SUPERINTENDENT, GOVERNMENT DAIRY FARM, KUDIGE, COORG DISTRICT.

Notification dated 21st January 1969.

It is hereby notified for the information of public that the old and unserviceable articles of the Government Dairy Farm, Kudige will be sold by public auction on Monday the 17th March, 1969 commencing from 10-30 A.M. by the undersigned at the premises of the Government Dairy Farm, Kudige subject to the terms and conditions of the sale. Intending bidders may inspect the articles at Government Dairy Farm, Kudige on any working day during the office hours. For any other particulars they may contact in person or in writing to this office. The terms and conditions are notified on the notice board of the Farm.

...., *Superintendent.*

2789

OFFICE OF THE COMMANDANT, M.A.R.P., PALACE GUARDS, MOUNTED COMPANY, MYSORE.

Tender Notification dated 18th February 1969

No. SC. FA. 1/68-69. It is hereby notified for the information of the Firms dealing in feed and other articles that sealed tenders superscribed "Tenders for the supply of feed and other articles to the Horses of the Police Department", for the financial year 1969-70, will be received by the undersigned in his office till 17th March 1969 upto 4 P.M. for the supply of articles detailed hereunder:—

Sl. No.	Description of Feed and other articles.	Approximate quantity
1	Horsegram well cleaned and free from all impurities	65,700 K. Gs.
2	Wheat bran fit for consumption of Horses.	49,275 ,,
3	Doubled crushed oats without any impurities.	32,850 ,,
4	White common-salt.	1,643 ,,
5	Hariyaligrass without thorns and any impurities (for feeding)	1,64,250 ,,
6	Paddy-straw well dried and fit for bedding of Horses.	1,31,400 ,,
7	Dindiga fuel well dried billets of ¾ meter (for boiling Horsegram).	36,500 ,,
8	Iron-horse shoe's (set of four)	1,080 Sets
9	Horse-shoeing nails (Swaeden) (No. 3)	40 K. Gs.
	(No. 4)	31 ,,
10	Lico/Charcoal fo Horse-shoeing (Good quantity) (40 Bags.)	1,200 ,,

Note: -Further details regarding terms and conditions of the Tender may be had from the office during office hours on working days.

2 Quotations should be for 100 Kgs.

279 KRISHNA K. R., *Commandant.*